

ASTA

CERTIFICATE OF TYPE TESTS

Laboratory Ref. No. **9424 2000023 708** Certificate No. **16932**

APPARATUS: 1000 A / 400 V / 500 V GL / 1 A_N / 0.5, 50 Hz Busbar (routing system, three-phase from busbar system + N and PE (housing))

DESIGNATION: DIN 40004

MANUFACTURER: GERSHAG Elektro-Technik GmbH A. B.
Tuna-Mechanische Gbg. San. Böğazi
Kartal cad. no. 5
P. O. BOX TUGLA-ISTANBUL,
TURKEY

TESTED BY: Institut „Professur elektrische Hochspannungstechnik“ Götting
Landsberger Allee 375A
37083 Götting, GERMANY

CATALOGUE OF TESTS: 01 September to 08 October 2000

The apparatus constructed in accordance with the description, drawings and photographs incorporated in this certificate has been subjected to the series of proving tests in accordance with:

EN 60439-2:2000-10, Sub-clauses 8.1.1, 8.2.2, 8.2.3, 8.2.4.2, 8.2.6, 8.2.7,
8.2.8, 8.2.9, 8.2.10, 8.2.12, 8.2.13, 8.2.14 and 8.2.15

The results are shown in the record of Proving Tests and the certificate attached hereto. The results obtained and the general performance are considered to comply with the above standards and to fully be design assigned by the manufacturer as stated below.

For ratings assigned by the manufacturer and proved by test see Pages 1 and 2.

The record of Proving Tests applies only to the apparatus tested. The responsibility for conformity of any apparatus having the same designations with that tested rests with the Manufacturer.

The Certificate covers: Drawings, 1 Reports, 4 Photographs, 12 Photographs, 2 Drawings
and/or other tests.

Any illegal reproduction of this Certificate, or reproduction of its parts incorporated in and signed in which are stated the assigned rated characteristics of the apparatus tested, are prohibited without written permission from ASTA, IASB Certification Services, 1000 Avenue Corporation Street, Maple, Massachusetts, 01860 USA, under copyright.



[Signature]
D. C. H. Lee

ASTA Director
& IASB
Certification
Manager

Date