TEST CONFIRMATION

on the given range of performed tests

GERSAN ELEKTRİK Tic. ve San. A.Ş. [illegible] [illegible] 34957 TUZLA-ISTANBUL TURKEY	CLIENT
GERSAN Elektrik Tic. ve San. A.Ş.	MANUFACTURER
1250 A / 400 V / 1000 V U_i / I_{cw} / I_{pk} 50 Hz Busbar trunking system, three-phase main busbar system 1 N and PE (4-pole)	TEST OBJECT
GE 1250A	TYPE
Test sample	SERIAL NO.
Rated operational voltage U_e 400 V AC Rated insulation voltage U_i 1000 V AC Rated current I_n 1250 A Rated short-time withstand current I_{cw} 50 kA / 1 s Rated peak withstand current I_{pk} 105 kA Rated frequency f 50 Hz Degree of protection IP55	RATED CHARACTERISTICS [illegible]
IEC 60439-2: 2000-11	NORMATIVE DOCUMENT
Verification of: - temperature-rise limits - the dielectric properties - the short-circuit withstand strength - the effectiveness of protective circuit - clearances and creepage distance - the degree of protection - EMC tests - the resistance of insulating materials to abnormal heat and fire - the electrical characteristics of the busbar trunking system - structural strength - crushing resistance - resistance to flame propagation - fire resistance in building penetration	RANGE OF TESTS PERFORMED
03 September to 16 October 2009	DATE OF TEST
The performance of the apparatus was considered satisfactory and subject to final analysis of the test results, verification of the assembly to drawings and scrutiny by Intertek Testing & Certification Ltd. an ASTA Certificate will be issued with respect to these tests. The test results are documented in the ASTA Certificate No. [illegible] Subcontract Ref. No.: [illegible]	TEST RESULT

[illegible]
ASTA Director

[illegible]
Test engineer in charge

Berlin, [illegible] November 2009

[illegible]

[illegible]